
Appendix A

(Description of Work Scope Items)

PTP Sanitary Sewer System

- Mobilization
- Sewer Construction & Installation
- Removal of Material
- Cleanup of Work Area & Stabilization

Scope work items are listed above & detailed below.

Mobilization:

Movement to site. All equipment must be cleaned ahead of time and inspected before moved to the site at Pioneer Trail Park.

Sewer Construction & Installation:

Construct and install: site sewer connections to 28 campground sites; 7 sites will gravity flow to a grinder pump & tank – pump to a manhole where flow gravity feeds with the remainder of the sites to a 2000-gallon septic tank and new drain-field. Mis-Dig must be contacted before work begins and contractor is responsible for all utilities damaged.

****Engineered specifications and drawings are available: Appendix “B”.**

Removal of Material:

All tree-stumps affected must be removed off site from Pioneer Trail Park. Resulting holes must be filled, top-dressed with top-soil and seeded.

Cleanup of Work Area & Stabilization:

All areas disturbed by construction must be free of debris, stabilized & landscaped to original ground elevation, top-dressed with top-soil and seeded.

Weather depended project (the DCD will dictate work dates). Scheduled for May 2019.